


- NOTES**
- 1.) CONSULT MANUFACTURER REPRESENTATIVE FOR MOTOR BLOWER HEIGHT AND OTHER SPECIFICATIONS.
 - 2.) UNITS MUST BE ATTACHED TO IN-PLANT COMPRESSED AIR SUPPLY FOR CLEANING MECHANISM TO FUNCTION (90 MAX. PSIG CLEAN DRY AIR)
 - 3.) VALVES AND CONTROL TIMER SYSTEM OPERATE ON 120V, 50-HZ. POWER.
 - 4.) WELDED STEEL CONSTRUCTION OF 12 GA. MILD STEEL.
 - 5.) SOLID STATE PULSE CONTROL TIMER IN NEMA 4 ENCLOSURE.
 - 6.) PAINTED INSIDE & OUT CRIMSON RED.
- SPECIFICATIONS**
- TOTAL VALVES: 8
- TOTAL CARTRIDGES: 16
- COMPRESSED AIR: 1.0 SCF @90 PSI PER SEC.



TITLE
RP8-2 BOLT
TOGETHER WITH
BLOWER DETAIL

**TOLERANCES UNLESS
OTHERWISE NOTED ON
3 DEC. PLACE**
SCALE: 1/2" = 1'-0"
DIM. DIMS.
1/32" = 10'

DMG. NO. 1564
REV. 2

DATE: 12-17-97
BY: JG
CHKD BY: JG
APP. 11

SH. 3 OF 4

METAL FAB
NEW VENTURA, CA 95728
NEW VENTURA, CA 95728