


- NOTES**
- 1.) CONSULT MANUFACTURER REPRESENTATIVE FOR MOTOR BLOWER HEIGHT AND OTHER SPECIFICATIONS.
 - 2.) UNITS MUST BE ATTACHED TO IN-PLANT COMPRESSED AIR SUPPLY FOR CLEANING MECHANISM TO FUNCTION (90 MAX PSIG CLEAN DRY AIR)
 - 3.) VALVES AND CONTROL TIMER SYSTEM OPERATE ON 120V, 50-HZ POWER.
 - 4.) WELDED STEEL CONSTRUCTION OF 12 GA. MILD STEEL.
 - 5.) SOLID STATE PULSE CONTROL TIMER IN NEMA 4 ENCLOSURE.
 - 6.) PAINTED INSIDE & OUT CRIMSON RED.
- SPECIFICATIONS**
- TOTAL VALVES 12
- TOTAL CARTRIDGES 24
- COMPRESSED AIR 1.0 SCF @90 psi per sec.



<p>TITLE</p> <p>RP8-3 BOLT TOGETHER WITH BLOWER DETAIL</p>		<p>TOLERANCES UNLESS SHOWN OTHERWISE</p> <p>3 DEC. PLACES 0.001</p> <p>SCALE 1/3"=1"</p>	
<p>DMC NO: 1564</p> <p>REV: 2</p>	<p>DATE: 12-17-97</p> <p>BY: JLD</p> <p>CHKD BY: DMC</p>	<p>SH. 4 OF 4</p>	<p>DMC NO: 1564</p> <p>REV: 2</p>